

Quantities shown are preliminary and meant for planning purposes only.

**Montana Department of Transportation
Preliminary Quantities**

Proj Number: Richey-Northeast

Prepared By:

UPN Number: 9179000

Date:

Design Stage: Plan In Hand Review

County: Richland

CostEstimate: 9179000RDEST001

District: Glendive

Type of Work:

Item Number	Quantity	Description	Unit
104030010	20,000.00	MISCELLANEOUS WORK	UNIT
104030065	200.00	MISCELLANEOUS ITEMS A-LNFT	LNFT
109200005	1.00	MOBILIZATION	LS
203020100	911,540.00	EXCAVATION-UNCLASSIFIED	CUYD
203080100	91,139.00	TOPSOIL-SALVAGING AND PLACING	CUYD
301020268	10,000.00	TRAFFIC GRAVEL	CUYD
301020340	100,794.00	CRUSHED AGGREGATE COURSE	CUYD
301020450	22,301.00	SPECIAL BACKFILL	CUYD
301020625	199,899.00	AGGREGATE TREATMENT	SQYD
302000000	137,669.00	PAVEMENT PULVERIZATION	SQYD
401020045	36,767.00	PLANT MIX SURF-3/4 IN	TON
401020046	1,044.00	PLANT MIX BIT SURF-MISC	TON
401020300	515.00	HYDRATED LIME	TON
402020090	1,947.30	ASPHALT BINDER PG 58H-34	TON
402020315	20,235.00	EMULSIFIED ASPHALT-TACK COAT	GAL
402020375	313.70	EMULSIFIED ASPHALT CHFRS-2P	TON
409000000	10.60	FINAL SWEEP AND BROOM	CRMI
409000010	173,988.00	COVER-TYPE 1	SQYD
411011125	10.60	CENTERLINE RUMBLE STRIPS-TYPE 2	MILE
411011135	21.20	RUMBLE STRIPS	MILE
551020030	275.20	CONCRETE-CLASS GENERAL	CUYD
551020120	377.00	CEMENT GROUT	CUYD
603000050	1,949.00	GRANULAR BEDDING MATERIAL	CUYD
603000060	2,200.00	FOUNDATION MATERIAL	CUYD
603010025	1.00	PLUG ENDS AND ABANDON PIPE	EACH
603010040	1,502.00	DRAINAGE PIPE 18 IN	LNFT
603010048	710.00	DRAINAGE PIPE 24 IN	LNFT
603010056	288.00	DRAINAGE PIPE 30 IN	LNFT
603010064	156.00	DRAINAGE PIPE 42 IN	LNFT
603010068	408.00	DRAINAGE PIPE 48 IN	LNFT
603010072	180.00	DRAINAGE PIPE 54 IN	LNFT
603010080	358.00	DRAINAGE PIPE 66 IN	LNFT
603010084	162.00	DRAINAGE PIPE 72 IN	LNFT
603010092	162.00	DRAINAGE PIPE 84 IN	LNFT

Montana Department of Transportation
Preliminary Quantities

603010100	110.00	DRAINAGE PIPE 96 IN	LNFT
603010714	96.00	CSP 96 IN	LNFT
603011827	470.00	SSPP 144 IN	LNFT
603012793	196.00	RCP 90 IN	LNFT
603013190	100.00	RCPA 18 IN EQ DIA	LNFT
603013212	98.00	RCPA 30 IN EQ DIA	LNFT
603013342	280.00	REIN CONC BOX 10 X 8	LNFT
603013381	164.00	REIN CONC BOX 12 X 8	LNFT
603013410	186.00	REIN CONC BOX 16 X 12	LNFT
603016085	168.00	CULVERT-LINER CONCRETE	LNFT
603587020	3,907.00	REMOVE PIPE CULVERT	LNFT
606010037	2.00	MASH BOX BEAM TERMINAL - MBEAT	EACH
606010040	576.00	GUARDRAIL-STEEL BOX BEAM	LNFT
606010385	1,874.00	REMOVE GUARDRAIL	LNFT
610100101	229.80	SEEDING AREA NO 1	ACRE
610100102	10.60	SEEDING AREA NO 2	ACRE
610100103	37.90	SEEDING AREA NO 3	ACRE
610100326	229.80	FERTILIZING AREA NO 1	ACRE
610100327	10.60	FERTILIZING AREA NO 2	ACRE
610100565	32,710.00	EROSION CONTROL BLANKET-HIGH-PERFORM	SQYD
610220050	10.60	MULCH-COMPOST	ACRE
611010300	3.00	RESET CATTLE GUARD	EACH
613100085	93.00	OUTLET APRON	SQYD
613100105	188.30	ANCILLARY ARMOR	CUYD
613520010	7,664.00	VEGETATED CONCRETE BLOCK MAT	SQYD
618030005	2,000,000.00	TRAFFIC CONTROL DEVICES CB	UNIT
620011105	10.00	WORDS AND SYMBOLS-WHITE PAINT	GAL
620011260	5.00	WORDS AND SYMBOLS-WHITE EPOXY	GAL
620012955	111,789.00	TEMPORARY STRIPING	LNFT
620013000	742.00	STRIPING-WHITE PAINT	GAL
620013960	511.00	STRIPING-WHITE EPOXY	GAL
620014000	464.00	STRIPING-YELLOW PAINT	GAL
620014960	319.00	STRIPING-YELLOW EPOXY	GAL
622011084	7,875.00	GEOTEXTILE STABILIZATION	SQYD
622011086	91,355.00	SEPARATION GEOTEXTILE - HIGH	SQYD