

Montana Department of Transportation
Preliminary Quantities

Proj Number: STPP 225-2(2)12
Cascade County Line - N

Prepared By: mdthq\U9433
Date: 5/9/2018 3:18:10 PM

UPN Number: 9519001

County: Chouteau

Design Stage: Alignment and Grade Review

District: Great Falls

CostEstimate: 9519001RDEST001

Type of Work:

Item Number	Quantity	Description	Unit
104030010		MISCELLANEOUS WORK	UNIT
105070000	1.00	CONTRACTOR SURVEY AND LAYOUT	LS
109200005	1.00	MOBILIZATION	LS
203020100	111,919.00	EXCAVATION-UNCLASSIFIED	CUYD
203020200	102,435.00	EXCAVATION-UNCLASS BORROW	CUYD
203020310	48,946.00	SPECIAL BORROW-NEAT LINE	CUYD
203080100		TOPSOIL-SALVAGING AND PLACING	CUYD
208010150		TEMPORARY EROSION CONTROL - LS	LS
208010200		TEMPORARY EROSION CONTROL	UNIT
301020268		TRAFFIC GRAVEL	CUYD
301020340	37,250.00	CRUSHED AGGREGATE COURSE	CUYD
301020625	103,293.00	AGGREGATE TREATMENT	SQYD
401020045	18,445.00	PLANT MIX SURF GR S-3/4 IN	TON
401020048		PLANT MIX SURF GR S-1/2 IN	TON
401020300	258.00	HYDRATED LIME	TON
402020092	940.50	ASPHALT CEMENT PG 64-28	TON
402020095		ASPHALT CEMENT PG 70-28	TON
402020315	10,441.00	EMULSIFIED ASPHALT-TACK COAT	GAL
402020320		EMULSIFIED ASPHALT-FOG SEAL	GAL
402020368	0.00	EMULSIFIED ASPHALT CRS-2P	TON
402020375	165.70	EMULSIFIED ASPHALT CHFRS-2P	TON
409000010	92,108.00	COVER-TYPE 1	SQYD
409000020		COVER-TYPE 2	SQYD
411010000	4,328.00	COLD MILLING	SQYD
411011135		RUMBLE STRIPS	MILE
603010040		DRAINAGE PIPE 18 IN	LNFT
603010048		DRAINAGE PIPE 24 IN	LNFT
603010066		DRAINAGE PIPE 36 IN	LNFT
606010023		ONE-WAY DEPART TERM SECTION	EACH
606010030		GUARDRAIL-STEEL	LNFT
606010040		GUARDRAIL-STEEL BOX BEAM	LNFT
606010047		GD RAIL-STL INT RDWY TERM SECT	LNFT
606010385		REMOVE GUARDRAIL	LNFT
606010641		GD RL BOX BEAM OPT TERM SEC	EACH

Montana Department of Transportation
Preliminary Quantities

606010642		GUARDRAIL-OPTIONAL TERM SECT	EACH
606011244		CONCRETE BARRIER RAIL	EACH
610100101		SEEDING AREA NO 1	ACRE
610100102		SEEDING AREA NO 2	ACRE
610100103		SEEDING AREA NO 3	ACRE
610100326		FERTILIZING AREA NO 1	ACRE
610100327		FERTILIZING AREA NO 2	ACRE
610100555		CONDITION SEEDBED SURFACE	ACRE
618030005	525,000.00	TRAFFIC CONTROL DEVICES CB	UNIT
620012950		TEMPORARY STRIPING	MILE
622011084	88,704.00	GEOTEXTILE STABILIZATION	SQYD