

JCT SEC 250-NORTH

CONSTRUCTION IMPROVEMENTS PLANNED ON MT 13
PROJECT OVERVIEW



VISION ZERO

zero deaths · zero serious injuries

MONTANA DEPARTMENT
OF TRANSPORTATION

PHASE 1

In 2019, MDT plans to replace the Box Elder Creek Bridge (near RP 20) due to the structure's age and deterioration. The new bridge will be a precast concrete bridge, meeting current design standards.

Traffic will be maintained on the existing bridge during construction.



PHASE 2

In 2021, MDT plans to rebuild the 8-miles of roadway to provide 12-foot travel lanes and 2-foot shoulders.

The road will be shifted to flatten the tight horizontal curves and the abrupt vertical curves. The timber bridge at the North Fork Box Elder Creek will be replaced with a concrete box culvert.

Traffic will be maintained on the existing roadway during reconstruction.



CONTACT INFO:



DJ Berg, MDT
406-444-2067
djberg@mt.gov



Kathy Harris, KLJ
406-441-5784
kathy.harris@kljeng.com